

**Kent County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
93 JUL 23 AM 10:30

For corners in

<u>Kent</u> <small>(County)</small>	Located In:	Corner Code #:	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S <u>15</u> T <u>10N</u> R <u>9W</u>	<u>Spencer Twp.</u>	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

W. J. Bond
REG. OF DEEDS
**Prop Control
other code # 1
6783**
Register of Deeds Stamp & File Number

I, John C. Bueche, in a field survey on June, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This point never set by G.L.O.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

W & W 1985 used computed angle from 1971 Section breakdown which was a straight line from SW cor. to SE cor. Existing iron was set 1324.96' (W & W) (1324.79' MBN) E of SE cor., Sec. 15; existing cor. is 0.95' N of a straight line. I propose that we hold this direction & mon. this point.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced iron with Std. K.C. Mon. (Harrison 4" x 30") in swamp
Nail & K.C. Remon. Tag S side 4" Cedar E 10.90'
Nail & K.C. Remon. Tag N side 6" Elm W 28.56'
Nail & K.C. Remon. Tag N side 6" Poplar N 75° W 22.13'
W edge of Lake East 80'±
Meas. by hand



Signed by John C Bueche Date June 10, 1993
Surveyor's Michigan License No. 13027