

**SURVEY &
RECORDATION**

MAY 09 1996

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Other

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED
93 SEP -7 11 11 55

COMMISSION

For corners in

Kent
(County)

Located In: Corner Code: #

- | | | |
|------------------------------------|--------------------------|-------------------------------|
| 1. Public Land Survey | T <u>10N</u> R <u>9W</u> | West witness monument to K-12 |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | <i>Other Code</i> |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | <i>#10</i> |
| | S _____ T _____ R _____ | |
| 4. Lot No. | Recorded Plat | |
| 5. Private Claims | | |

6833

(Register of Deeds Stamp & File Number)

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		22
7													
8	19		20		21		22		23		24		
9													
10	30		31		32		33		34		35		36
11													
12	31		32		33		34		35		36		
13													

I, Wallace E. Glaza, in a field survey on July 9, 19 93 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
No previous history.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

West witness monument to K-12, T10N, R9W, Spencer Township, Kent County, Michigan.

Set standard 4" x 30" Harrison Monument 13' West of waters edge of Half Mile Lake on a straight line between the center of Section 35 and the 1/4 corner as established for the SE 1/4 of Section 35 and SW 1/4 of Section 36.

Witness corner is 1569.59 feet East of the center of Section 35.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

West witness monument to K-12 (4" x 30" standard Harrison Monument)

- 1) Nail and tag in E side 12" Oak N30°E 16.99'
- 2) Nail and tag in E side 18" Oak S45°W 7.12'
- 3) Nail and tag in NE side 24" Twin Oak S05°W 40.35'
- 4) Nail and tag in NW side 18" Oak S85°W 11.46'
- 5) NE'rly corner of house No. 13800 Pinewood St S30°W 124.81'



Signed by Wallace E. Glaza
Glaza and Associates, Inc.
Surveyor's Michigan License No. 31592

Date 8-12-93