

MAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

~~T 10N R 11W~~ M-3 Solon Twp.
T R Common
T 10N R 10W A-3 Nelson Twp.
T R
S T R
S T R
S T R
S T R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECORDED

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:00

11112
Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 9, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-3 1837	GLO	Brookfield	Set Post
1875	Williams & Works		Found Stake per gov't. wits.
1961	Kent Co. Wits		1" Iron
1981	LCRC #3564	VanKooten	1" Iron in Mon. Box
1992	LCRC #6598	Bueche	Set Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10-12-92 and was recorded per LCRC #6598.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-3 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the 1" Iron he found in a Mon. Box. Said Iron checks with Kent Co. Wit. and LCRC #3564.

LCRC #6598
Nail & Remon. tag NE side P. Pole N50°W 46.79'
Nail & Remon. tag SW side P. Pole S55°E 60.27'
"X" cut in curb S70°W 47.47'
"X" cut in curb S30°W 49.32'
C/L Tel. Box N45°E 41.93'
On C/L bit. N-S and on C/L gravel E-W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-3 Standard Kent County Monument in Mon. Box
Nail & KC Remon. tag NE side P. Pole N50°W 46.79'
Nail & KC Remon. tag SW side P. Pole S55°E 60.27'
"X" cut in curb S70°W 47.51'
"X" cut in curb S30°W 49.32'
C/L Tel. Box N45°E 41.93'
On C/L N-S asphalt road and on C/L E-W gravel road ±



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99