

MAY 22 2000

KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in:

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

~~T10N R 11W~~ M-6 Solon Twp.  
~~T10N R 10W~~ A-6 Nelson Twp.

2. Property Controlling in Section

S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-6 1836	GLO	Brookfield	Set Post
1938	Kent Co. Wits		1" Iron & Stone
1980	LCRC #1416	Hackbardt	Mon. Box
1981	LCRC #2077	Nederveld	3"4 Iron in Mon. Box
1992	LCRC #6599	Bucche	Set Kent County Monument in Mon. Box

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/25/99  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bucche on 10-12-92 and was recorded per LCRC #6599.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bucche in place of the 3/4" Iron Pipe he found inside a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC's #1416 & #2077  
LCRC #6599

"X" cut on top CMP	N10°E	107.12'
"X" cut on top CMP	N10°W	108.49'
Nail & Remon. tag SW side 8" Ash	S60°E	82.96'
Nail W. side P. Pole	S15°E	119.12'
NW cor. conc. pad MBT box		118.81'

On C/L bit. N-S, on C/L gravel East

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Standard Kent County Monument

"X" cut on top CMP	N10°E	107.12'
"X" cut on top CMP	N10°W	108.49'
Nail & Remon. tag S. side 12" Ash	S70°E	104.30'
Nail & KC Remon. tag SW side 10" Ash	S60°E	82.96'
Nail W. side P. Pole	S15°E	118.95'
NW corner of pad for Ameriteck Box	S25°E	118.81'



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 2/25/99

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 MAR 24 AM 09:19  
REG. CLERK  
11115  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												