

MAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 JUL -9 AM 11:19

11247

Register of Deeds Stamp & File Number

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey
 - ~~T 10N R 11W~~ ~~M-8 Solon~~
 - T R Common
 - T 10N R 10W A-8 Nelson
 - T R
- 2. Property Controlling in Section
 - S T R
 - S T R
- 3. Miscellaneous Property in Sec.
 - S T R
 - S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on May 17, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- M-8 1837 GLO Brookfield Set Post
- 1966 Kent Co. Wits 1" Iron
- 1973 LCRC #489 Spicer Boat Spike
- 1982 LCRC #3123 Merdzinski Set Kent County Monument
- 1990 LCRC #5596 Marschall Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/24/99
CHAIRMAN Henry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 10-18-82 and was recorded per LCRC #3123.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the Boat Spike over a 60d Nail over a 1" Square Iron he found. All check with Kent Co. Wit. and LCRC #489.

- | | | | |
|------------|---|------------|---|
| LCRC #3123 | Nail & Remon. tag P. Pole N60°W 97.33' | LCRC #5596 | Nail & Remon. tag P. Pole N60°W 97.37' |
| | Nail & Remon. tag Elec. Pole N90°W 76.90' | | Nail & Remon. tag Elec. Pole N90°W 76.80' |
| | Face of 3" Steel Mail Box Post S80°E 15.45' | | Top C/L 4" De-watering pump S73°W 66.17' |
| | C/L blacktop road is 2' West of corner | | 2" Steel gate post, C/L base N85°W 45.50' |
| | C/L driveway running West is 15' North | | |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-8 Standard Kent County Monument
- Nail & KC Remon. tag NE side P. Pole S60°W 97.42'
- Nail & KC Remon. tag N. side Elec. Serv. Pole N90°W 76.80'
- Top C/L 4" De-watering pump S73°W 66.17'
- Face Steel Mail Box Post - at grade S75°E 16.65'
- C/L blacktop road is 2' West of corner
- C/L driveway to West is 15' North



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 6/24/99