

MAY 22 2000

\$7.00
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T10N R 11W M-11 Solon Twp.
T R Common
T10N R 10W A-11 Nelson Twp.
T R
- 2. Property Controlling in Section S T R
S T R
- 3. Miscellaneous Property in Sec. S T R
S T R

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 9, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 9:00
REG. OF RECORDS

11118
Register of Deeds Stamp & File Number

A. Description of original monument and accessories and/or subsequent restoration:

- M-11 1837 GLO Brookfield Set Post
- 1939 Kent Co. Wits Iron in Mon. Box
- 1971 LCRC #86 Spicer 1" Iron in Mon. Box
- 1978 LCRC #1207 Jonker Iron in Mon. Box
- 1981 LCRC #2007 Jonker Set Kent County Monument in Mon. Box
- 1990 LCRC #5598 Marschall Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8-20-81 and was recorded per LCRC #2007.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Iron he found in a Mon. Box. Said Iron checks with Kent Co. Wits. and LCRC's #86 & #1207.

LCRC #2007	SE corner bldg. (corner stone)	N43°W 53.63'	Nail & Remon. tag	Guy Pole	S15°E 100.91'
	C/L Hydrant	S53°W 53.92'	Top Hydrant		S50°W 54.07'
	C/L Manhole	West 18.04'	SE corner building stone ledge		N45°W 53.62'
	C/L Manhole	East 17.83'	Nail & MDOT tag	Guy Pole	N25°E 56.70'
	C/L Manhole	N38°E 24.76'	Nail & Remon. tag	U.P.	N75°E 99.25'
	C/L Manhole	S18°W 49.44'			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-11 Standard Kent County Monument in Mon. Box
- Nail & KC Remon. tag W. side Guy Pole S15°E 100.79'
- C/L top of fire hydrant S50°W 54.00'
- SE corner building stone ledge N45°W 53.66'
- Nail & MDOT tag E. side Guy Pole N25°E 56.70'
- Nail & KC Remon. tag N. side Util. Pole N75°E 99.27'
- NW corner sign base S55°E 65.33'
- At C/L intersection ±



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99