

SURVEY &  
REMONUMENTATION  
DATE  
MAY 22 2000

\$7.00  
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

~~T10N R 11W~~ M-12 Solon Twp.  
T10N R 10W A-12 Nelson Twp.

2. Property Controlling  
in Section

T R  
T R  
S T R  
S T R  
S T R  
S T R

3. Miscellaneous  
Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-12 1837	GLO	Brookfield	Set Post
	Kent Co. Wits		3/8" Iron
1972	LCRC #336	Spicer	PK nail and tag in 1" Iron
1978	LCRC #1207	Jonker	PK nail & MSHD tag
1981	LCRC #2008	Jonker	Set Kent County Monument
1990	LCRC #5599	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/25/99  
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 8-20-81 and was recorded per LCRC #2008.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-12 Found Kent County Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the PK Nail he found over a 1/2" Solid Rod. Both PK & Solid Rod checks with LCRC's #336 & #1207 and Kent Co. Wits.  
LCRC #2008 LCRC #5599

"I" Iron West 36.34'	Nail & Remon. tag 26" Maple S48°W 53.60'
Nail & MSHD tag 36" Maple N89°W 36.14'	Nail & Remon. tag 30" Maple S32°W 77.56'
Nail & Remon. tag 18" Maple S48°W 53.62'	Nail & Remon. tag 16" Maple S70°W 40.72'
Nail & Remon. tag 18" Maple S32°W 77.57'	Nail & Remon. tag P. Pole N90°W 57.33'
C/L N. end drive culv. S20°E 76.00	C/L N. end dr. culv. S20°E 76.05'
C/L const. joint - West 3.4' m/l	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-12 Standard Kent County Monument

Nail & KC Remon. tag E. side 32" Maple	S48°E 56.65'
Nail & KC Remon. tag E. side 32" Maple	S32°W 77.62'
Nail & KC Remon. tag N. side 20" Maple	S70°W 40.69'
Nail & KC Remon. tag N. side new P. Pole	N85°W 60.67'
SW corner concrete base for sign	N35°W 91.50'
C/L N. end drive culvert	S20°E 76.0'
C/L paint stripe is West 1.5' ±	



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 2/25/99

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 MAR 24 AM 8:00

11119

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													