

MAY 22 2000

\$7.00
\$2.00

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Nelson Township	Corner Code #
1. Public Land Survey	T <u>10N</u>	R <u>10W</u>	<u>F-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
 1999 DEC - 8 AM 10: 01
 REG. OF DEEDS

11517

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Randy Kolehouse, in a field survey on January 26 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13	1837	G.L.O. Notes	Cathcart	Set Post
	1968	Records	Consumers Power Company	Large "T" Iron
	1985	L.C.R.C. #4051	Exxel Engineering	Large "T" Iron
	1986	L.C.R.C. #4446	Randy Kolehouse	Fnd. "T" Iron / Set K.C. Monument
	1993	L.C.R.C. #6701	John Bueche	K.C. Monument

Note: This corner is not common with F-1, T9N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse May of 1986 and was recorded per L.C.R.C. #4446.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13 Found a Standard Kent County Monument on the C/L of 16 Mile Road (gravel) running East and West, 5' ± West of the C/L of Stout Avenue (gravel) running North, and 29' ± West of Stout Avenue (bit.) running South per L.C.R.C.'s #4446 and #6701 as set by Randy Kolehouse in place of a 5' long "T" type steel fence post he found which checked L.C.R.C. #4051 and the 1968 records of Consumers Power.

L.C.R.C. #4446

L.C.R.C. #6701

Nail & K.C. Remon. tag in E. side 18" Hick. N15° W 80.54'
 Nail & K.C. Remon. tag in W. side P.Pole N 50° E 90.96'
 Nail & K.C. Remon. tag in N. side P.Pole S 70° W 150.89'
 K.C. Mon. at N1/4 cor sec 4 T 9 N R 10 W East 35.41'

Nail & K.C. Remon. Tag in E side 20" Hickory N 15° W 80.54' (m. 80.47')
 Nail & K.C. Remon. Tag in W side PP N 50° E 90.96' (m. 90.88')
 Nail & K.C. Remon. Tag in N side PP S 70° W 150.84' (m. 150.82')
 NE cor. hse. Fnd. S 60° E 217.75' (m. 217.73')
 NW cor. hse. Fnd. S 45° E 161.29' (m. 161.25')
 K.C. Mon. (N 1/4 4, 9-10) East 35.55' (m. 35.53')

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13 Standard Kent County Monument

Nail & K.C. remon. tag on E side 24" Hickory N 15° W 80.47'
 Nail & K.C. remon. tag on W side P. pole N 50° E 90.88'
 Nail & K.C. remon. tag on N side P. pole S 70° W 150.82'
 NE cor. hse. Fndn. S 60° E 217.73'
 NW cor. hse. Fndn. S 45° E 161.25'
 On C/L of gravel road running E-W

C/L of gravel road running N, East 5' ±
 C/L of bit. road running S, East 29' ±
 K.C. Mon., F-1, T9N, R10W, East 35.53'

Signed by Randy Kolehouse Date 10/28/99

WILLIAMS & WORKS

Surveyor's Michigan License No. 25854

