

MAY 22 2000

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 DEC - 8 AM 10: 01

REG. OF DEEDS

11518

Register of Deeds Stamp & File Number

For corners in

| Kent (County) | Located in: Nelson Township | Corner Code # |
|---------------------------------------|--------------------------------|---------------|
| 1. Public Land Survey | T <u>10N</u> R <u>10W</u> | G-13 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Randy Kolehouse, in a field survey on January 21 19 99, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

| G-13 | 1837 | G.L.O. Notes | Cathcart | Set Post |
|------|------|----------------|-----------------|--|
| | 1937 | Witness Map | K.C. Surveyor | Conc. Monument |
| | 1986 | L.C.R.C. #4445 | Randy Kolehouse | Fnd. 3/4" Iron / Set K.C. Monument in Mon. Box |
| | 1993 | L.C.R.C. #6712 | John Bueche | K.C. Monument in Mon. Box |

Note: This corner is not common with G-1, T9N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Randy Kolehouse in May of 1986 and was recorded per L.C.R.C. #4445.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 Found a Standard Kent County Monument in a monument box 23' ± West of the C/L intersection of Myers Lake Avenue (bit.) running North and South and 16 Mile Road (gravel) running East and West per L.C.R.C.'s #4445 and #6712 as set by Randy Kolehouse in place of a 3/4" iron he found in a monument box which checked the K.C. Surveyor's records.

L.C.R.C. #4445

L.C.R.C. #6712

Nail & K.C. Remon. tag in N. side 16" Walnut S 70° W 61.33'
Nail & K.C. Remon. tag in S. side 16" Ash N 80° W 52.3'
Nail & K.C. Remon. tag in W. side 10" Ash N 45° E 77.51'
K.C. Mon. at NE cor. sec. 4 T 9 N R 10 W East 23.10'

Nail & K.C. Remon. Tag in S side 16" Ash N 80° W 52.30' (m. 52.34')
Nail & K.C. Remon. Tag in N side 10" Poplar S 75° E 92.99' (m. 92.95')
Nail & K.C. Remon. Tag in W side 6" Elm N 20° W 43.99' (m. 44.01')
Nail & K.C. Remon. Tag in N side 16" Walnut S 70° W 61.33' (m. 61.32')
Nail & K.C. Remon. Tag in W side 12" Ash N 45° E 77.48' (m. 77.50')
K.C. Mon. (NE 4, 9-10) East 23.28' (m. 23.22')
C/L bit. N-S, E 23'+/-
On C/L bit.-gravel E-W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Standard Kent County Monument in a Monument Box

Nail & K.C. remon. tag on N side 16" Walnut S 70° W 61.32'
Nail & K.C. remon. tag on S side 16" Ash N 80° W 52.34'
Nail & K.C. remon. tag on N side 10" Poplar S 75° E 92.95'
Nail & K.C. remon. tag on W side 6" Elm N 20° W 44.01'
Nail & K.C. remon. tag on W side 12" Ash N 45° E 77.50'

On C/L of gravel road running E-W
C/L of bit. road running N-S, East 23' ±
K.C. Mon., G-1, T9N, R10W, East 23.22'

Signed by

Randy J. Kolehouse
WILLIAMS & WORKS

Date

10/28/99

Surveyor's Michigan License No.

25854

