

\$7.00 MONUMENTATION
\$2.00

SEP 18 1995

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey	T	10N	R	10W	H-12
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Section	S		T	R	
	S		T	R	

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 JUL 11 PM 1:53
REG. OF DEEDS
Luis Standa
85333

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on July 5, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-12	1837	GLO	Not Set
	1968	Consumers Power Co.	Set "T" Iron at "X" 1/4 lines
	1974	Kent Co. Wits	"T" Iron

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/22/95
CHAIRMAN *Harry Thubert*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-12 Found Re-rod (in asph. rd.) over large "T" Iron per witnesses of Consumers Power Co. & Kent Co. Wit. Said Rerod over "T" Iron is less than 0.1' in any direction from the "X" of 1/4 lines. The Re-rod and "T" Iron has also been used in other surveys by various surveyors.

<u>Consumers Power Co.</u>	<u>Kent Co. Wit.</u>
10" Maple N 50.30'	10" Maple N 50.30'
18" Maple SW 15.15'	18" Maple SW 15.15'
10" Tw. Maple NE 64.23'	10" Tw. Maple NE 64.23'
C/L grav. rd. is N. 14'	18" W. Cherry S 28.02'
	C/L grav. rd. is N. 14'

The Re-rod over the "T" Iron is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-12 Set Standard Kent County Monument in place of Re-rod over large "T" Iron

Set Nail & KC Remon. tag E. side 18" Maple	N00°E	50.37'
Set Nail & KC Remon. tag S. side Db1. 18" Maple	N60°E	64.06'
Set Nail & KC Remon. tag W. side 10" Oak	S00°E	30.22'
Set Nail & KC Remon. tag NW side 6" Poplar	S40°E	50.39'
C/L Asph Rd. is North 8' m/l		



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 7/6/95