

SURVEY & REMONUMENTATION

MAY 22 2000

LAND CORNER RECORDATION CERTIFICATE
SECTION Filing Requirement of Act 74, Mich. P.A. 1970
KENT COUNTY REMONUMENTATION

For corners in

Kent (County)	Located in:	Nelson Township	Corner Code #
1. Public Land Survey	T <u>10N</u>	R <u>10W</u>	<u>J-13</u>
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

REG. OF DEEDS
 1999 DEC - 8 AM 10: 01
 STATE OF MICHIGAN
 COUNTY OF KENT
 RECEIVED FOR RECORD
11521
 Register of Deeds Stamp & File Number

I, Randy Kolehouse, in a field survey on February 11 1999, do hereby certify that under requirements of P.A. 74 Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13	1837	G.L.O. Notes	Cathcart	Set Post
	1978	L.C.R.C. #1236	William Byl	Large "T" Iron
	1980	L.C.R.C. #1748	Williams & Works	Fnd. "T" Iron / Set K.C. Monument
	1988	L.C.R.C. #4765	John Bueche	K.C. Monument

Note: This corner is not common with J-1, T9N, R10W.

This corner was originally approved by the Kent County Remonumentation Peer Group and monumented by Williams & Works on 12/17/80 and was recorded per L.C.R.C. #1748.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13 Found a Standard Kent County Monument on the C/L of 16 Mile Road (gravel) running East and West, on line of a tree row running North, per L.C.R.C.'s #1748 and #4765 as set by Williams & Works in place of a large "T" iron they found over a stone 3-1/2' below ground which checked L.C.R.C. #1236.

L.C.R.C. #1748

- K.C. Remon. Tag & Nail in NE Side 18" Walnut N 80°W 108.28'
- K.C. Remon. Tag & Nail in S Side 10" Elm S 65°E 48.73'
- K.C. Remon. Tag & Nail in W Side 16" Oak S 05°E 185.13'
- K.C. Remon. Tag & Nail in S Side P. Pole S 65°W 180.46'
- K.C. Remon. Tag & Nail in NW Side 6" Elm S 35°W 34.96'

L.C.R.C. #4765

- K.C. Remon tag & nail in NE sde 18" Walnut N 80 W 108.16' (m. 108.28')
- K.C. Remon tag & nail in S sde 10" Elm S 65 E 48.70' (m. 48.73')
- K.C. Remon tag & nail in W sde 16" Oak S 05 E 184.67' (184.91')
- K.C. Remon tag & nail in S sde P. Pole S 65 W 180.46' (m. 180.40')
- K.C. Remon tag & nail in NW sde 6" Elm S 35 W 34.86' (m. 35.00' stump)
- "X" cut on top of culvt N 17 E 24.75' (m. 24.86')
- On gravel C/L rd E & W

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13 Standard Kent County Monument

- Nail & K.C. remon. tag on NE side 20" Walnut N 80° W 108.28'
- Nail & K.C. remon. tag on S side 10" Elm S 65° E 48.73'
- Nail & K.C. remon. tag on S side P. pole S 65° W 180.40'
- Nail & K.C. remon. tag on W side 20" Oak S 05° E 184.91'
- Nail & K.C. remon. tag on W side 10" Elm S 10° W 24.04'
- "X" cut top N end culvert N 17° E 24.86'

- On C/L of gravel road running E-W
- On tree row running N
- K.C. Mon., J-1, T9N, R10W, East 284.85'

Signed by Randy Kolehouse
 WILLIAMS & WORKS
 Surveyor's Michigan License No. 25854

Date 10-29-99

