

JAN 24 1996 KENT COUNTY REMONUMENTATION

COMMISSION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY (County)

Located In:

Corner Code #

- 1. Public Land Survey T10N R10W K-2
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

Register of Deeds Stamp & File Number. Includes date 95 SEP 14 PM 12:36 and handwritten signature.

I, Kirk Breitels, in a field survey on July 12, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A black dot is present in cell J2.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- K-2 1837 GLO Cathcart Set Post ? Kent Co. Wit.
1896 Williams & Works Stake(s) same as 1966 Williams & Works
1900 Williams & Works Stake 1988 LCRC #4544 Jonker
1966 Williams & Works Bt. Spike in Iron Boat Spike in Iron
24" Stump E 18.85' Tw. 25" Maple West 40.55'
10" Maple SW 28.75' 36" Maple clp. S55°E 50.91'
10" Maple W 40.68' 12" Maple N75°E 32.72'
On old fence line W.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-2 Found 3/4" Iron at road surface (top mangled - no boat spike). Iron fits all witnesses (+) from 1962 Williams & Works information and LCRC #4544. Iron is on C/L gravel road N-S ± and on traces of fence to E & W.

Meas. N. to NW cor. Sec. 1 (Conc. Mon.) 3106.37' - 1900 Williams & Works = 3103.3'
Meas. N. to fence line W. and tree row E. 1333' ± - 1900 Williams & Works = 1335.6'

The 3/4" Iron Pipe is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-2 Set Standard Kent County Monument in place of the 3/4" Iron Pipe.
Set Nail & KC Remon. tag NW side 12" Maple S35°W 40.41'
Set Nail & KC Remon. tag N. side Tw. 27" Maple S90°W 40.55'
Set Nail & KC Remon. tag W. side 15" Maple N35°W 35.21'
Set Nail & KC Remon. tag N. side 15" Maple N70°E 32.73'
Set Nail & KC Remon. tag S. side clump 8"-12" Maples S70°E 19.12'
Set Nail & KC Remon. tag W. side 18" Ash S45°E 72.56'

P.A. 345 1990 KENT COUNTY
PEER APPROVED 8/24/95
CHAIRMAN Harry Hubert



Signed by Kirk Breitels Date 9/8/95
30077