

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Kent	Located In:	Corner Code //
County		
1. Public Land Survey	T <u>10N</u> R <u>10W</u>	L-12
	T _____ R _____	
	T _____ R _____	
	T _____ R _____	
2. Property Controlling in Section	S _____ T _____ R _____	
	S _____ T _____ R _____	
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	
	S _____ T _____ R _____	
4. Lot No. _____	Recorded Plat _____	
5. Private Claims _____		

93/10/25 10:05

6817

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Wallace E. Glaza, in a field survey on August 4, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration.**

No previous history.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

L-12 (center of Section 36, T10N, R10W, Nelson Township, Kent County, Michigan)  
 Found iron pipe. Verified pipe to be 1.00' North and 0.17' East of intersection of  $\frac{1}{4}$  lines. Accepted iron pipe as center.  
 Replaced iron pipe with standard 4" x 30" Harrison Monument.

South  $\frac{1}{4}$  corner to center - 2639.93'  
 West  $\frac{1}{4}$  corner to center - 2627.93'  
 North  $\frac{1}{4}$  corner to center - 2666.92'  
 East  $\frac{1}{4}$  corner to center - 2639.29'

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

L-12 (standard 4" x 30" Harrison Monument)

1) Nail and tag in West side 10" Oak	N00°E	69.12'
2) Nail and tag in NW side 10" Oak	S40°W	90.88'
3) Nail and tag in NW side 20" Maple	S70°W	85.26'
4) Nail and tag in East side 6" Pine	S20°W	65.63'



Signed by Wallace E. Glaza Date 8-9-93  
 Glaza and Associates, Inc. 31592  
 Surveyor's Michigan License No. \_\_\_\_\_