

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>19</u> T. <u>10</u> N. R. <u>11</u> W.		B-9
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. S., R. _____, E. W.		E 1/8 Cor., SW Frl. 1/4
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. S., R. _____, E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 19 80, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>B-9 Found 1" Pinched Pipe. Measured distances matched distances reasonably from data on corner witness map from Williams and Works.</p>	<p>E 1/8 Cor., SW Frl. 1/4, Section 19 Set 4" x 36" concrete monument half way and on line between B-8 and B-9. Pulled iron 3.74 South that did not fit existing government corners.</p>
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>B-9 S 1/4 Corner, Section 19 Found 1" Pinched Pipe S 84° W, 54.72', 10" Ironwood, Square Nail N 58° W, 80.45', 8" & 9" Ash, Square Nail West, 72', East Bank Duke Creek North, 72', South Bank Duke Creek East, 80', West Bank Duke Creek South, 133', Bottom of Hill Slope</p>	<p>E 1/8 Cor., SW Frl. 1/4, Section 19 Set 4" x 36" concrete monument in C of Sherwin Road. S 35° E, 46.56', NE Tower Leg S 65° W, 38.18', 18" R. Pine, Spike & Tag N 52° W, 37.92', Twin 16" Maple, Spike & Tag N 63° E, 83.40', Power Pole, Spike & Tag</p>
--	---

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Ronald L. Bissell DATE 11-20-80
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655