

**SURVEY &
REMONUMENTATION**

MAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 10N R 12W	Tyrone Twp M-1
	T ___ R ___	Common
	T 10N R 11W	Solon Twp A-1
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

REG. OF DEEDS

[Handwritten Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 NOV -4 AM 8:37

11510

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 23, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-1 1837	GLO	Brookfield	Set Post
	Kent Co. Wits		Iron
1983	LCRC #3609	Hackbardt	Set 1/2" Rerod on Twp. line 2933.45' West of B-1 Solon per W & W
1985	LCRC #4379	Ochs	Set Kent County Monument on Twp. Line
1991	LCRC #6037	Byl	Kent County Monument

P.A. 845 1990 KENT COUNTY

PEER APPROVED 9/23/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Norman L. Ochs on 12-6-85 and was recorded per LCRC #4379.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 Found Kent County Monument (Harrison) per witnesses from above LCRC as set on Twp. Line by Norman L. Ochs at the same location as LCRC #3609 (set after road construction).

LCRC #4379		LCRC #6037	
Spike in 14" Red Oak	N20°E 35.58'	Nail & Remon. tag 16" Red Oak	N20°E 35.54'
Spike in 4" Twin Ironwood	N25°W 85.38'	Nail & Remon. tag Twin 4" Ironwood	N25°W 85.20'
Spike in 4" Maple	South 49.93'	Nail & Remon. tag 4" Maple	S00°W 49.90'
Spike in 8" Red Oak	S65°E 82.31'	Nail & Remon. tag 12" Red Oak	S65°E 82.27'
S 1/4 cor. Sec. 31-11-11	East 185.32'	Cast Iron Mon. (S 1/4 cor. Sec. 31-11-11)	N90°E 185.20'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1 Standard Kent County Monument		
Nail & KC Remon. tag N. side 16" Red Oak	S65°E	82.27'
Nail & KC Remon. tag S. side P. Pole (8' high)	N65°E	82.44'
Capped Rerod	N55°W	42.08'
Nail & KC Remon. tag N. side 27" Oak	S70°W	101.15'
Nail & KC Remon. tag W. side 12" Oak	S05°W	49.96'
S 1/4 cor. Sec. 31-11-11 (Newaygo Co. Mon.)	East	185.28'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 10/28/99