

SURVEY & REMONUMENTATION

MAY 22 2000

KENT COUNTY REMONUMENTATION

\$7.00  
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 MAR 21 AM 9:04

REG. OFFICERS

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

1. Public Land Survey

~~T10N R 12W~~ ~~M-5 Tyrone Twp.~~  
T \_\_\_ R \_\_\_  
Common  
~~T10N R 11W~~ ~~A-5 Solon Twp.~~  
T \_\_\_ R \_\_\_

2. Property Controlling in Section

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous Property in Sec.

11203

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

|    |    |   |    |   |    |   |    |   |    |   |    |   |   |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

I, Kirk Breitels, in a field survey on Jan. 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

|          |               |            |                          |
|----------|---------------|------------|--------------------------|
| M-5 1837 | GLO           | Brookfield | Set Post                 |
| 1965     | Kent Co. Wits |            | 1" Iron                  |
| 1974     | LCRC #717     | VanKooten  | 1" Iron in Mon. Box      |
| 1983     | LCRC #3244    | Byl        | Set Kent County Monument |
| 1991     | LCRC #6041    | Byl        | Kent County Monument     |

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/25/99  
CHAIRMAN Harry Fisher

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 2-28-83 and was recorded per LCRC #3244.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-5 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 1" Iron Pipe next to a 3/4" Iron in a Mon. Box he found. All check with Kent Co. Wits. and LCRC #717.  
LCRC #3244  
Nail & Remon. tag 24" Oak N40°E 45.72'  
Nail & Remon. tag 18" Oak S30°E 41.83'  
Nail & Remon. tag C.P. Pole N60°W 145.89'  
Nail & Remon. tag 12" Pine S50°W 42.90'  
C/L B.T. is 3' North  
LCRC #6041  
Nail & Remon. tag 30" Oak N40°E 45.76'  
Nail & Remon. tag 24" Oak S30°E 41.83'  
Nail & Remon. tag C.P. Pole N60°W 145.78'  
Nail & Remon. tag 12" Pine S50°E 42.84'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-5 Standard Kent County Monument  
Nail & KC Remon: tag W. side 30" Oak N40°E 45.76'  
Nail & KC Remon. tag N. side 24" Oak S30°E 41.63'  
Nail & KC Remon. tag N. side C.P. Pole N60°W 145.78'  
Nail & KC Remon. tag N. side 14" Pine S50°W 42.84'  
C/L E-W blacktop road is North 3' ±



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/25/99