

MAY 22 2000

KENT COUNTY REMONUMENTATION

\$7.00
\$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- 1. Public Land Survey

T 10N R 12W	M 6 Tyrone Twp.
T ___ R ___	Common
T 10N R 11W	A-6 Solon Twp.
T ___ R ___	
- 2. Property Controlling in Section

S ___ T ___ R ___	
S ___ T ___ R ___	
- 3. Miscellaneous Property in Sec.

S ___ T ___ R ___	
S ___ T ___ R ___	

REG. OF DEEDS

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 21 AM 9:04

11204

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-6 1837	GLO	Brookfield	Set Post
	Kent Co. Wits		Stake
1981	LCRC #1621	Hackbardt	Set 1/2" Rerod per original witnesses
1983	LCRC #3245	Byl	Set Kent County Monument
1991	LCRC #6042	Byl	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by William R. Byl on 3-31-83 and was recorded per LCRC #3245.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-6 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by William R. Byl in place of the 1/2" Rerod he found. Said Rerod checks with LCRC #1621.	
LCRC #3245	LCRC #6042
Nail & Remon. tag 16" Oak N05°E 55.67'	Nail & Remon. tag 20" Oak N05°E 55.70'
Nail & Remon. tag 12" Pine N60°W 24.63'	Nail & Remon. tag 12" Pine N60°W 24.56'
Nail & Remon. tag 16" Oak N90°E 22.09'	Nail & Remon. tag 18" Oak N90°E 22.09'
Nail & Remon. tag 20" Aspen S00°W 33.77'	Nail & Remon. tag 24" Aspen S00°W 32.88'
	Nail & Remon. tag Tw. 24" Oak N10°W 33.31'
	Nail & Remon. tag 27" Oak N90°E 1.96'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-6 Standard Kent County Monument	
Nail & KC Remon. tag W. side 24" Oak	N05°E 55.74'
Nail & KC Remon. tag N. side 12" Pine	N60°W 24.60'
Nail & KC Remon. tag N. side 18" Oak	N90°E 22.12'
Nail & KC Remon. tag W. side Tw. 24" Oak	N10°W 33.35'
Nail & KC Remon. tag S. side 30" Oak	N90°E 1.96'
Nail & KC Remon. tag SE side 20" Poplar	S45°W 35.92'



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99