

MAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located in:

Corner Code #

- 1. Public Land Survey T10N R12W M-8 Tyrone Twp. Common A-8 Solon Twp.
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

REG. OF DEEDS

1999 JUL -9 AM 11:20

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

11261

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Kirk Breitels, in a field survey on May 26, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-M and rows 1-13. Contains numbers 6-36 in a grid pattern.

A. Description of original monument and accessories and/or subsequent restoration:

- M-8 1837 GLO Brookfield Set Post
Kent Co. Wits 2" Iron
1980 LCRC #1413 Bissell 1 1/2" Pipe - raised with 120d Nail
1986 LCRC #4457 Kolehouse Set Kent County Monument
1991 LCRC #6003 Byl Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 6/24/99
CHAIRMAN Randy Kolehouse

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 4-5-86 and was recorded per LCRC #4457.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-8 Found BROKEN Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse in place of the 120d Nail over an Iron he found. Both check with Kent Co. Wits. and LCRC #1413.

- LCRC #4457 LCRC #6003
Nail & DNR tag 14" Ash S28°W 55.92' Nail & DNR tag 18" Ash S28°W 55.95'
Nail & Remon. tag 16" Oak S84°W 25.97' Nail & Remon. tag 18" Oak S84°W 25.93'
Nail & Remon. tag 8" Twin Oak S45°E 43.38' Nail & Remon. tag 12" Twin Oak S45°E 43.33'
60d Nail Tri. 12" Oak N21°W 49.60' 60d Nail Tri. 10"-18" Oak N21°W 49.57'
60d Nail 16" Oak S23°E 52.55' 60d Nail 18" Oak S23°E 52.55'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-8 Removed and Reset Standard Kent County Monument
Nail & DNR tag E. side 20" Ash S28°W 55.95'
Nail & KC Remon. tag N. side 22" Oak S84°W 25.93'
Nail & KC Remon. tag N. side 12" Twin Oak S45°E 43.33'
Nail & KC Remon. tag E. side Tri. 10"-18" Oak N21°W 49.57'
Nail & KC Remon. tag W. side 22" Oak S23°E 52.52'
In C/L N-S gravel road ±
On N. edge of wood line to East ±



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 6/24/99