

~~\$7.00~~  
~~\$2.00~~  
MAR 08 1999

KENT COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAR -5 AM 8:31  
REG. OF DEEDS  
*Lucy Staud*

For corners in SECTION \_\_\_\_\_

KENT COUNTY Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

(County)

1. Public Land Survey ~~T-0N R-12W~~ ~~M-1 Sparta~~  
T-\_\_\_ R-\_\_\_ common with  
~~T-0N R-11W~~ ~~A-1 Algoma~~  
~~T-10N R-12W~~ ~~M-13 Tyrone~~  
2. Property Controlling S-\_\_\_ T-10N R-11W ~~A-13 Solon~~  
in Section S-\_\_\_ T-\_\_\_ R-\_\_\_  
3. Miscellaneous S-\_\_\_ T-\_\_\_ R-\_\_\_  
Property in Sec. S-\_\_\_ T-\_\_\_ R-\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

10495  
Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, Kirk Breitels, in a field survey on Jan. 5, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

M-1	1837	GLO	Brookfield	Set Post
	1939	Kent Co. Wits		Concrete Monument
	1949	Williams & Works		Concrete Monument
	1992	LCRC #6611	Bueche	Set Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/19/98  
CHAIRMAN John C. Bueche

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10-12-92 and was recorded per LCRC#6611.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-1 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Concrete Monument he found. Concrete Monument checks with Kent Co. Wits. and Williams & Works information.  
LCRC #6611  
Nail & Remon. tag SW side 10" Oak N45°W 7.89'  
Nail & Remon. tag W. side 18" Oak N35°E 26.69'  
Nail & Remon. tag SW side 16" Oak S40°E 32.25'  
Nail & Remon. tag SW side 18" Oak S30°E 44.01'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-1	Standard Kent County Monument		
	Nail & KC Remon. tag SW side 12" Oak	N45°W	7.88'
	Nail & KC Remon. tag W. side 20" Oak	N35°E	26.67'
	Nail & KC Remon. tag SW side 18" Oak	S40°E	31.97'
	Nail & KC Remon. tag SW side 20" Oak	S30°E	43.83'



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 2/19/98