

\$7.00
\$2.00

MAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 DEC 17 AM 8:01

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Solon Twp.

1. Public Land Survey	T 10NR 11W	B-2
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

11616

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Oct. 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

B-2 1837	GLO	Not Set
1911	Williams & Works	Set Center of Section by Section Survey
	Kent Co. Wits	No information
1986	Survays Hackbardt	Shows "Iron Set" symbol at Center of Section & another survey shows straight E-W 1/4 line.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 10/28/99
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-2 Established Intersection of 1/4 lines and found position to be on large concrete footing of corner fence post - fence post being 0.4' NW'ly.

Measurements agree ± with those by Hackbardt, Roosien, and Glaza

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-2 Drilled Rerod with "Kent Co. Remon." cap into concrete footing of fence post	
"V" cut on SE leg of Consumers Energy tower	N85°E 25.27'
Nail & KC Remon. tag NE side 16" Poplar	N15°W 41.67'
Nail & KC Remon. tag S. side 12" Poplar	N80°W 37.26'
Nail & KC Remon. tag SE side 16" Beech	S45°W 59.60'
Fence corner post is NW 0.4'	



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 12/15/99