

Survey &
RECORDATION

MAY 22 2000

\$7.00
\$2.00

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Solon Twp.

1. Public Land Survey

T 10N R 11W

B-8

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S ___ T ___ R ___

S ___ T ___ R ___

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

S ___ T ___ R ___

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Sept. 27, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- B-8 1837 GLO Not Set
- 1910 Williams & Works Set Pine Root Stake
- Kent Co. Wits No information
- 1980 LCRC #1414 Bissell Found 1/2" Iron Rod - "checks Williams & Works data"
- West 116.60' 30" W. Pine S09°E 105.0' NE leg of Transmission Tower
- S52°E 2.5' Fence Corner Post N45°E 161.08' 22" W. Oak

P.A. 345 1990 KENT COUNTY
PEER APPROVED 10/28/99
CHAIRMAN Harry Hubert

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- B-8 Found 1/2" Iron Rod with fitting per the remaining witnesses:
- NE leg of Transmission Tower S09°E 105.0'
- Nail & DNR tag 28" Oak N45°E 161.08'

Said 1/2" Iron Rod is 0.1' W. and 4.4' S. of intersection of 1/4 lines and was used by DNR surveyors (Bissell)

The 1/2" Iron Rod is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- B-8 Set Standard Kent County Monument in place of the 1/2" Iron Rod
- C/L East bolt on NE corner tower leg S10°E 105.00'
- Nail & KC Remon. tag NW side 30" Oak N40°E 161.04'
- Nail & KC Remon. tag N. side cluster 15" Maples S80°W 83.74'
- Nail & KC Remon. tag N. side 24" Oak N60°W 112.22'
- North face of DNR sign post South 1.35'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 12/6/99

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3		2	1
3													
4	7			8			9			10		11	12
5													
6	18			17			16			15		14	13
7													
8	19			20			21			22		23	24
9													
10	30			29			28			27		26	25
11													
12	31			32			33			34		35	36
13													

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 DEC 15 AM 8:55
REG. OF DEEDS

11585

Register of Deeds Stamp & File Number