

\$7.00 SEP 18 1995
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
95 MAY 12 AM 10:43

Lucy Bond
REG. OF DEEDS

For corners in
KENT COUNTY

(County)	Located In:	Corner Code ##
1. Public Land Survey	T 10N R 11W	B-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

8361

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on March 14, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
B-11 1837 GLO Cathcart Set Post
1967 Kent Co. Wit. Boat Spike
1979 LCRC #1274 Stadt 1 1/4" Iron in mon. box
1981 LCRC #2108 Jonker Set Kent County Monument in mon. box
1994 Glaza Witness Kent Co. Mon. before road const.

P.A. 345 1990 KENT COUNTY
PEER APPROVED 4/27/95
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9/9/81 and was recorded per LCRC #2108.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
B-11 Found 1/2" Iron in mon. box (after road const.). Set standard Kent Co. Mon. (Harrison) in mon. box in place of said 1/2" Iron per witnesses from Glaza and above LCRC as set by Robert J. Jonker in place of the 1 1/4" Iron he found inside a mon. box. Said Iron checks with Kent Co. Wit. and LCRC #1274.

LCRC #2108

Remon. tag SE side 12" Tw. Oak	S65°W	71.73'	(71.64' - Glaza - new nail)
Remon. tag SW side 16" oak	N60°W	89.03'	(88.94' - Glaza - new nail)
Remon. tag SW side P. Pole	N25°W	61.98'	(61.98' - Glaza)
Remon. tag S. side 24" Oak	N80°E	124.15'	(124.15' - Glaza - new nail)
C/L N-S tower line - E. - 20' m/l			
C/L B.T. - S. - 3' m/l			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
B-11 Standard Kent County Monument in mon. box
Nail & KC Remon. tag SE side 14" Tw. Oak S65°W 71.65'
Nail & KC Remon. tag SW side 18" oak N60°W 89.04'
Nail & KC Remon. tag SW side P. Pole N25°W 62.01'
Nail & KC Remon. tag S. side 30" Oak N80°E 124.26'
C/L N-S tower line - E. - 20' m/l
C/L B.T. - S. - 3' m/l



Signed by *Kirk Breitels*
30077

Date 4/20/95

Surveyor's Michigan License No. _____