

SEP 18 1995

\$7.00 COMMISSION  
\$2.00

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

95 MAY 12 AM 10:43

For corners in  
KENT COUNTY  
(County)

Located In: Corner Code #

- 1. Public Land Survey T 10N R 11W C-6
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

*Lucy Bond*  
REG. OF DEEDS

8367

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 21, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-6	1837	GLO	Cathcart	Set Post
	1901	Williams & Works		Set Stone & Pine Root
		Kent Co. Wit.		Stone
	1983	LCRC #3681	Bueche	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 12/6/83 and was recorded per LCRC #3681

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Re-rod he found. Said Re-rod checks with Williams & Works information  
LCRC #3681

KC Remon. tag & nail W. side 6" Ash	S15°E	65.06'	P.A. 345 1990 KENT COUNTY
KC Remon. tag & nail E. side group 8"-12" Maples	S15°W	75.14'	PEER APPROVED 4/27/95
KC Remon. tag & nail N. side (7' up) 12" Oak	S85°W	36.70'	CHAIRMAN <i>[Signature]</i>
KC Remon. tag & nail S. side 12" Oak	N25°W	43.73'	
Cap & Nail E. side 8" Pine	S40°W	58.37'	
On field division East, on C/L blacktop N-S			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-6 Standard Kent County Monument			
New KC Remon. tag & nail W. side 10" Ash	S15°E	65.04'	
New KC Remon. tag & nail E. side group 10"-16" Maples	S15°W	75.17'	
KC Remon. tag & nail N. side (7' up) 18" Oak	S85°W	36.74'	
New KC Remon. tag & nail S. side 18" Oak	N25°W	43.88'	
KC Remon. tag & nail SE side 12" Pine	S40°W	58.38'	
On field division East, on C/L blacktop N-S			



Signed by *[Signature]* Date 4/20/95  
Surveyor's Michigan License No. 30077