

\$7.00 SEP 18 1995  
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

55 MAY 12 AM 10:44

For corners in  
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>11W</u>	C-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

*W. J. Bond*

REG. OF DEEDS

8369

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Kirk Breitels, in a field survey on Feb. 21, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-8	1837	GLO	Cathcart	Set Post
		Kent Co. Wit.		Stone at fence intersection
	1981	LCRC #1418	Hackbardt	3/4" Iron
	1981	LCRC #2110	Jonker	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9/11/81 and was recorded per LCRC #2110.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Iron he found. Said Irons checks with Kent Co. Wit. and LCRC #1418.

LCRC #2110

Remon. tag E. side 9" Ash	N20°E	9.85'
Remon. tag NE side 6" Tw. Maple	S31°E	11.45'
Remon. tag N. side 8" Tw. Basswood	S75°E	5.84'
Remon. tag SE side 6" Poplar	S48°W	38.39'

P.A. 345 1990 KENT COUNTY

PEER APPROVED 4/27/95

CHAIRMAN *Harry Huber*

At intersection of fences to E, S, W and fence and tree row North  
A 4 way fence corner is 50' East m/I

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8 Standard Kent County Monument

New Nail & KC Remon. tag E. side 15" Ash	N20°E	9.80'
New Nail & KC Remon. tag NE side 8" Tw. Maple	S31°E	11.47'
New Nail & KC Remon. tag N. side 10" Tw. Basswood	S75°E	5.81'
New Nail & KC Remon. tag SE side 10" Poplar	S48°W	38.40'
Set Nail & KC Remon. tag N. side 30" Poplar	N80°W	11.15'
At intersection of fences to E, S, W and fence and tree row North		
A 4 way fence corner is 50' East m/I		



Signed by Kirk Breitels  
Surveyor's Michigan License No. 30077

Date 4/20/95