

MAR 08 1999

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN COUNTY OF KENT RECEIVED FOR RECORD

98 JUL 14 AM 9:54

\$7.00 \$2.00

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in KENT COUNTY

Located In: Corner Code #

Table with 3 columns: Section description, Located In (Town/Range), and Corner Code #. Includes entries for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

Handwritten signature and 'REG. OF DEEDS' stamp

10650

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Kirk Breitels, in a field survey on June 22, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column C and row 13.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Table listing monument details: C-13 1837 GLO Brookfield Set Post, 1907 Williams & Works Fence Corner, 1941-53 Williams & Works Iron, 1980 Survey N. Ochs 1/2" Iron per Williams & Works, 1992 LCRC #5486 VanKooten 1/2" Pipe, 1996 LCRC #9588 Breitels Set Kent County Monument

P.A. 345 1990 KENT COUNTY PEER APPROVED 6/25/98 CHAIRMAN Harry Stuber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Kirk Breitels on 12-12-96 and was recorded per LCRC #9588.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Kirk Breitels in place of the 1/2" Iron Pipe he found. Said Iron Pipe checks with Williams & Works, N. Ochs and LCRC #5486.

Table listing corner evidence: Nail & Remon. tag E. side 10" Oak S20°W 6.70', Nail & Remon. tag S. side 6" Oak S60°E 3.07', Nail & Remon. tag E. side 6" Cherry N20°W 21.71', Nail & Remon. tag W. side 6" Oak N20°E 21.56', Nail & Remon. tag SE side Tri. 10" Maple N45°E 53.30', Kent Co. Mon. at C-1 Algoma Twp. - West 299.84'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Table listing monument details: C-13 Standard Kent County Monument, Nail & KC Remon. tag E. side 10" Oak S20°W 6.70', Nail & KC Remon. tag S. side 6" Oak S60°E 3.07', Nail & KC Remon. tag E. side 6" Cherry N20°W 21.71', Nail & KC Remon. tag W. side 6" Oak N20°E 21.56', Nail & KC Remon. tag SE side Tri. 10" Maple N45°E 53.30', Kent Co. Mon. at C-1 Algoma Twp. West 299.87'



Signed by [Signature] 30077
Surveyor's Michigan License No.

Date 6/25/98