

SEP 18 1995

COMMISSION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

\$7.00
\$2.00

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

95 MAY 12 AM 10:44

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
T <u>10N</u> R <u>11W</u>	D-1
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____
S _____ T _____ R _____	_____

David J. Bond
REG. OF DEEDS

8374

Register of Deeds Stamp & File Number

- Public Land Survey
- Property Controlling in Section
- Miscellaneous Property in Sec.
- Lot No. _____, Recorded Plat _____
- Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Feb. 21, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-1	1837		Not Set
		Kent Co. Wit.	Stone
	1909	Williams & Works	Stone
	1985	LCRC #4382	Ochs
			Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Norman L. Ochs on 11/14/85 and was recorded per LCRC #4382.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Norman L. Ochs at a point he set on the twp. line. Said point checks with Williams & Works information.

LCRC #4382

28" White Oak	N50°E	55.09'	Spk. SE side
30" Maple	N70°E	118.21'	Spk. SE side
P. Pole	S45°E	73.45'	Spk. N. side
SE corner Sec. 32 West 70.8'			

P.A. 345 1990 KENT COUNTY

PEER APPROVED 4/27/95

CHAIRMAN *Harry Hubert*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 Standard Kent County Monument

New Nail & KC Remon. tag SE side	36" White Oak	N50°E	55.12'
Nail & KC Remon. tag SE side	32" Maple	N70°E	118.23'
New Nail & KC Remon. tag N. side	P. Pole	S45°E	73.57'
SE corner Sec. 32, Ensley Twp.		West	70.80'



Signed by *Kirk Breitels* Date 4/20/95

Surveyor's Michigan License No. 30077