

MAY 22 2000

\$7.00  
\$2.00

SECTION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

REG. OF DEEDS

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 DEC 15 AM 8:55

For corners in

KENT COUNTY  
(County)

Located In:

Corner Code #

Solon Twp.

- 1. Public Land Survey      T 10 N R 11 W  
   T \_\_\_\_\_ R \_\_\_\_\_  
   T \_\_\_\_\_ R \_\_\_\_\_  
   T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling      S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
   in Section                    S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
   Property in Sec.            S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

11587

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Oct. 15, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

D-4 1837	GLO	Not Set
	Williams & Works	No information
	Kent Co. Wits	No information

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 10/28/99  
CHAIRMAN [Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-4 Established Intersection of 1/4 lines and found nothing. 4-way fence corner is 6' East and 4' South

Measurements agree ± with Hackbart (straight E-W 1/4 line - no Center set)

The Intersection of 1/4 lines is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-4, Set Standard Kent County Monument at the Intersection of 1/4 lines.
- Nail & KC Remon. tag N. side 20" Hickory      S70°W    7.47'
- Nail & KC Remon. tag W. side 18" Oak            N20°E    20.60'
- Nail & KC Remon. tag N. side 15" Ash            N60°W    47.64'
- Nail & KC Remon. tag W. side 12" Ash            S00°E    33.48'
- Nail & KC Remon. tag N. side 18" Oak            N90°E    22.27'
- 4-way fence corner is 6' East & 4' South



Signed by [Signature]  
Surveyor's Michigan License No. 30077

Date 12/6/99