

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

SEP 18 1995
\$7.00
\$2.00 COMMISSION

95 MAY 12 AM 10:44

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Lee J. Bond
REG. OF DEEDS

For corners in
KENT COUNTY
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>11W</u>	D-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

8376

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 21, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-5	1837	GLO	Cathcart	Set Post
	1967	Kent Co. Wit.		"T" Iron
	1980	LCRC #1480	VanLaar	Square Bolt
	1981	LCRC #2100	Jonker	Set Kent County Monument in mon. box

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9/8/81 and was recorded per LCRC #2100.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Iron he found inside a mon. box (6" below rd.). Said Iron checks with Kent Co. Wit. & LCRC #1480.

LCRC #2100

Remon. tag N. side	10" Maple	S65°E	71.28'
Remon. tag W. side	6" Elm	N15°E	49.25'
Remon. tag E. side	12" Poplar	S28°E	57.48'
Iron	South 60.03'		
C/L E-W B.T.	- North 4.5' m/I		

P.A. 345 1900 KENT COUNTY
PEER APPROVED 4/27/95
CHAIRMAN *Harry J. Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5	Standard Kent County Monument		
Set Nail & KC Remon. tag	S. side 8" Maple	N75°E	103.16'
Set Nail & KC Remon. tag	NE side 6" Poplar	S60°E	49.54'
Set Nail & KC Remon. tag	NW side 14" Willow	S50°W	38.43'
Iron	- South 60.03'		
C/L E-W B.T.	- North 4.5' m/I		



Signed by *Kirk Breitels*

Date 4/20/95

Surveyor's Michigan License No. 30077