

**SURVEY &
REMONUMENTATION**

MAY 22 2000

**\$7.00
\$2.00**

KENT COUNTY REMONUMENTATION

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>KENT COUNTY</u> (County)	Located In:	Corner Code #
	Solon Twp.	D-10
1. Public Land Survey	<u>T</u> <u>10N</u> <u>R</u> <u>11W</u>	<u> </u>
	<u>T</u> <u> </u> <u>R</u> <u> </u>	<u> </u>
	<u>T</u> <u> </u> <u>R</u> <u> </u>	<u> </u>
	<u>T</u> <u> </u> <u>R</u> <u> </u>	<u> </u>
2. Property Controlling in Section	<u>S</u> <u> </u> <u>T</u> <u> </u> <u>R</u> <u> </u>	<u> </u>
	<u>S</u> <u> </u> <u>T</u> <u> </u> <u>R</u> <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	<u>S</u> <u> </u> <u>T</u> <u> </u> <u>R</u> <u> </u>	<u> </u>
	<u>S</u> <u> </u> <u>T</u> <u> </u> <u>R</u> <u> </u>	<u> </u>

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

1999 NOV - 4 AM 8:35

REG. OF DEEDS

11456

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breiteis, in a field survey on Aug. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-10 1837 GLO Not Set
- Williams & Works No information
- 1937 Kent Co. Wits Hub on part of plow
- 6" Hickory ESE 101.5' 6" W. Ch. SSW 188.25' 6" Ash WSW 113.6' 24" Maple NW 71.1'
- 1979 LCRC #1285 Reda Found Solid Iron
- 12" Hickory ESE 101.5' 24" Maple NW 71.1' C.P. N45°E 126.85'

P.A. 345 1930 KENT COUNTY
PEER APPROVED 8/26/99
CHAIRMAN Harry Huber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- D-10 Found Capped Rod (over another steel object lying sideways, 20" deep), per the following remaining witnesses:
- Fd. Nail N. side 16" Hickory S70°E 102.04' Fd. Nail SW side 30" Maple N45°W 71.78'
- Fd. PK Nail SE side P. Pole N40°E 126.79'

Said Capped Rod is 3.5' S. & 8.8' W. from intersection of 1/4 lines and has been used in surveys by Reda, Hackbart, Roosien, Griffin, Hay and Nederveld.

The Capped Rod is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- D-10 Set Standard Kent County Monument in Mon. Box in place of the Capped Rod
- Northerly corner house foundation S45°W 186.08'
- Nail & KC Remon. tag SW side 30" Maple N45°W 71.78'
- Nail & KC Remon. tag SE side P. Pole N40°E 126.79'
- Nail & KC Remon. tag N. side 16" Hickory S70°E 102.04'
- In C/L road intersection N-S & E-W ±



Signed by Kirk Breiteis
Surveyor's Michigan License No. 30077

Date 10/20/99