

\$7.00 SEP 18 1995
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 MAY 12 AM 10:44

Luigi Bond
REG. OF DEEDS

For corners in
KENT COUNTY

(County)	Located In:	Corner Code =#
1. Public Land Survey	T <u>10N</u> R <u>11W</u>	D-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

8379

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kirk Breitels, in a field survey on March 10, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-11	1837	GLO	Cathcart	Set Post	R.A. 345 1990 KENT COUNTY
		Kent Co. Wit.		Boat Spike	PEER APPROVED <u>4/27/95</u>
	1973	LCRC #563	VanKooten	Boat Spike	CHAIRMAN <u>Harry Fisher</u>
	1981	LCRC #2106	Jonker	Set Kent County Monument in mon. box	
	1994		Glaza	Witness Kent Co. Mon. before const.	

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9/9/81 and was recorded per LCRC #2106.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-11 Found empty mon. box. Set standard Kent Co. Mon. (Harrison) in mon. box per witnesses from Glaza and from above LCRC as set by Robert J. Jonker in place of the 1" Iron he found inside a mon. box. Said Iron checks with Kent Co. Wit. and LCRC #563.
LCRC #2106

Remon. tag E. side 32" Oak	N08°W	139.37'	(139.40' - Glaza)
Remon. tag SE side Tel. Pole	N41°E	70.66'	(70.66' - Glaza)
Remon. tag SW side P. Pole	S55°E	55.20'	(53.40' - Glaza - different pole)
Remon. tag S. side 12" Tw. Oak	South	53.15'	(53.11' - Glaza)
Remon. tag N. side P. Pole	S82°W	115.00'	(115.00' - Glaza)

Corner is 1' South of C/L "X" B.T.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-11 Standard Kent County Monument in mon. box			
Remon. tag & nail E. side 36" Oak	N08°W	139.37'	
Remon. tag & nail SE side Tel. Pole	N41°E	70.66'	
Remon. tag & nail SW side P. Pole	S55°E	53.43'	
Remon. tag & nail S. side 15" Tw. Oak	S00°E	53.17'	
Remon. tag & nail N. side P. Pole	S82°W	115.00'	

Corner is 1' South of C/L "X" B.T.



Signed by Kirk Breitels

Date 4/20/95

Surveyor's Michigan License No. 30077