

\$7.00 SEP 18 1995
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

95 MAY 12 AM 10:44

W. J. Bond
REG. OF DEEDS

For corners in
KENT COUNTY

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>11W</u>	D-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

8380

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 21, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13	1837	GLO	Cathcart	Set Post
	1973	LCRC #564	VanKooten	1" Iron
	1980	LCRC #1504	Merdzinski	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 12/10/80 and was recorded per LCRC #1504

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1" Iron he found in a ring of stones. Said Iron checks with LCRC #564

LCRC #1504

KC Remon. tag & nail S. side 16" Cherry	S70°E	22.20'
KC Remon. tag & nail NW side 4" Oak	S50°E	21.02'
KC Remon. tag & nail W. side 8" Oak	S20°W	15.37'
KC Remon. tag & nail N. side 8" Oak	N40°W	17.42'
KC Remon. tag & nail E. side 8" W. Cherry	N15°E	49.55'
SE cor. block hse.	N80°W	125.38'
Well Point - to face	N55°W	0.42'
Remains of fence line E-W - South 4'		

P.A. 345 1990 KENT COUNTY
PEER APPROVED 4/27/95
CHAIRMAN *Harry Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13 Standard Kent County Monument

New KC Remon. tag & nail S. side 16" Cherry	S70°E	22.20'
New KC Remon. tag & nail W. side 8" Oak	S20°W	15.37'
Set KC Remon. tag & nail E. side 10" Beech	N00°E	23.85'
Set KC Remon. tag & nail NW side 8" Poplar	S35°E	18.37'
Set KC Remon. tag & nail NE side 15" Oak	N45°W	8.84'
NE cor. steel pole bldg.	S50°W	34.52'
SE cor. block hse.	N80°W	125.38'
Well Point - to face	N55°W	0.42'
Remains of fence line E-W - South 4'		



Signed by *Kirk Breitels*

Date 4/20/95

Surveyor's Michigan License No. 30077