

\$7.00 SEP 18 1995
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

5 MAY 12 AM 10:44

For corners in
KENT COUNTY
(County)

Located In: Corner Code -#

1. Public Land Survey	T 10N R 11W	E-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Eric J. Bond
REG. OF DEEDS

8381

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 22, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1	1837	GLO	Cathcart	Set Post
	1909	Williams & Works		Gas Pipe
		Kent Co. Wit.		Iron
	1985	LCRC #4383	Ochs	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Norman L. Ochs on 7/1/85 and was recorded per LCRC #4383.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Norman L. Ochs in place of the 1" Pipe he found. Said 1" Pipe checks with Kent Co. Wit. & Williams & Works information.

LCRC #4383

Tel. Riser	N10°E	38.42'	(slope to top)
St. sign	S45°E	35.00'	
5" Elm	S55°W	72.91'	Spk. NE side

S 1/4 cor. Sec. 33, Ensley Twp., Newaygo Co. is West 110.50'

Note: Did not adjust to be on Newaygo Co. Standard line because the Meander Cor. of Gilbert Lake was not found or set.

P.A. 345 1990 KENT COUNTY

PEER APPROVED 4/27/95

CHAIRMAN *Harvey Hubers*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1 Standard Kent County Monument

Set Nail & KC Remon. tag S. side P. Pole	N70°W	112.38'
Set Nail & KC Remon. tag NW side P. Pole	S70°W	95.19'
Set Nail & KC Remon. tag E. side 4" Ash	N10°W	32.43'
Set Nail & KC Remon. tag W. side 12" Hickory	S30°W	84.85'
Top of Tel. Box (slope dist.)	N10°E	38.42'
S 1/4, Sec. 33, Ensley Twp., Newaygo Co.	West	110.50'



Signed by Kirk Breitels

Date 4/20/95

Surveyor's Michigan License No. 30077