

\$7.00 SEP 13 1995  
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
95 MAY 12 AM 10:44

*Lucy Bond*  
REG. OF DEEDS

8386

Register of Deeds Stamp & File Number

For corners in  
KENT COUNTY  
(County)

Located In:

Corner Code #

- |                                       |                         |       |
|---------------------------------------|-------------------------|-------|
| 1. Public Land Survey                 | T 10N R 11W             | E-6   |
|                                       | T _____ R _____         | _____ |
|                                       | T _____ R _____         | _____ |
|                                       | T _____ R _____         | _____ |
| 2. Property Controlling in Section    | S _____ T _____ R _____ | _____ |
|                                       | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____ |
|                                       | S _____ T _____ R _____ | _____ |
| 4. Lot No. _____, Recorded Plat _____ |                         |       |
| 5. Private Claims _____               |                         |       |

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Kirk Breitels, in a field survey on Feb. 22, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-6	1837	GLO	Cathcart	Set Post
	1965	Kent Co. Wit.		"T" Iron
	1983	LCRC #3236	Bonnema	"T" Iron
	1984	LCRC #3744	Meyer	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Allan L. Meyer on 2/21/84 and was recorded per LCRC #3744.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Allan L. Meyer in place of the "T" Iron he found. Said "T" Iron checks with Kent Co. Wit. and LCRC #3236.  
LCRC #3744

Nail & KC Remon. tag S. side 26" W. Cherry	S42°E	32.24'
Nail & KC Remon. tag SW side 24" Oak	S34°E	49.91'
Nail & KC Remon. tag E. side 12" Ash	S42°W	43.83'
Nail & KC Remon. tag N. side 4 - 6" Ash	West	43.22'
Nail & KC Remon. tag E. side 24" W. Cherry	N18°W	81.30'
Nail & KC Remon. tag N. side 10" Ash	N56°E	18.12'

STATE OF MICHIGAN  
KENT COUNTY  
PEER APPROVED 4/27/95  
CHAIRMAN *Harry Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 Standard Kent County Monument

New Nail & KC Remon. tag S. side 30" W. Cherry	S42°E	32.21'
New Nail & KC Remon. tag SW side 28" Oak	S34°E	49.96'
New Nail & KC Remon. tag E. side 16" Ash	S42°W	43.90'
New Nail & KC Remon. tag N. side 4 - 8" Ash	N80°W	43.23'
New Nail & KC Remon. tag E. side 30" W. Cherry	N18°W	81.14'
New Nail & KC Remon. tag N. side 14" Ash	N56°E	18.11'
Capped Iron (G.S.H.) - West		33.00'



Signed by *Kirk Breitels*

Date 4/20/95

Surveyor's Michigan License No. 30077