

\$7.00 SEP 18 1995
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

95 MAY 12 AM 10:45

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

W. J. Bond
REG. OF DEEDS

For corners in
KENT COUNTY
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>11W</u>	E-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

8388

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 22, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

E-8	1837	GLO	Cathcart	Set Post
	1980	LCRC #2084	Nederveld	Set Capped Iron
	1982	LCRC #2905	Jonker	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 6/10/82 and was recorded per LCRC #2905.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-8 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Capped Iron he found. Said Capped Iron checks with LCRC #2084 and physical evidence and information from county surveyors office.

LCRC #2905

Remon. tag W. side 12" Maple	S75°E	39.10'
Remon. tag N. side 10" Maple	N65°W	14.8'
Remon. tag E. side 12" Maple	N15°W	44.95'
Remon. tag N. side 8" Maple	S80°E	38.10'
Remon. tag SE side 12" Beech	S30°W	72.10'
On E. edge of N-S 2 track		

P.A. 345 1990 KENT COUNTY

PEER APPROVED 4/27/95

CHAIRMAN *Harry Hubers*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-8 Standard Kent County Monument

New Nail & KC Remon. tag W. side 18" Maple	S25°E	39.06'
New Nail & KC Remon. tag N. side 18" Maple	N65°W	14.90
New Nail & KC Remon. tag E. side 16" Maple	N15°W	44.96'
New Nail & KC Remon. tag N. side 10" Maple	S80°E	37.86'
New Nail & KC Remon. tag SE side 15" Beech	S30°W	72.14'
On E. edge of N-S 2 track		



Signed by *Kirk Breitels*

Date 4/20/95

Surveyor's Michigan License No. 30077