

CURTIS &
FRANK INVESTIGATION

\$7.00
\$2.00

MAY 22 2000

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

Solon Twp.

1. Public Land Survey

T 10N R 11W

F-8

2. Property Controlling
in Section

S

T R

3. Miscellaneous
Property in Sec.

S

T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Nov. 10, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-8 1837 GLO Not Set
Williams & Works No information
Kent Co. Wits No information
1987 LCRC #4496 Hackbardt Found 1/2" Rebar at intersection of 1/4 lines.
36" Oak N60°W 17.3' 15" Maple N70°E 27.4' 12" Oak S30°E 34.0'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-8 Found 1/2" Capped Rebar (Hackbardt) per the remaining witnesses:
Spike NE side 40" Oak N60°W 17.32' Spike S. side 18" Maple N70°E 27.37'
Spike SW side 14" Oak S30°E 33.95'

Said 1/2" Capped Rebar (Hackbardt) is 0.6' N. and 0.1' E. from intersection of 1/4 lines.

The 1/2" Capped Rebar (Hackbardt) is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-8 Set Standard Kent County Monument in place of the 1/2" Capped Rebar (Hackbardt)
Large Spike SW side 14" Oak S30°E 33.95'
Nail & KC Remon. tag S. side 15" Maple S90°E 32.68'
Nail & KC Remon. tag E. side 10" Beech S30°W 11.26'
Large Spike NE side 40" Oak N60°W 17.32'
Large Spike S. side 18" Maple N70°E 27.37'
Corner is at fence corner South & East ±

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 DEC 17 AM 8:00
REG. OF DEEDS
11621

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

P.A. 345 1990 KENT COUNTY
PEER APPROVED 12/02/99
CHAIRMAN Harry Huber



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 12/15/99