

SEP 13 1995  
\$7.00  
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

95 MAY 12 AM 10:45

*W. J. Bond*  
REG. OF DEEDS

For corners in  
KENT COUNTY  
(County)

Located In: Corner Code #

1. Public Land Survey	T 10N R 11W	F-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

8397

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Feb. 24, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

F-9	1837	GLO	Cathcart	Set Post
		Kent Co. Wit.		Iron
	1981	LCRC #2084	Nederveld	Nail
	1982	LCRC #2906	Jonker	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 6/9/82 and was recorded per LCRC #2906.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-9 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the Rerod & cap (Nederveld) he found. Said Rerod and cap checks with Kent Co. Wit. and LCRC #2084.

LCRC #2906

Remon. tag E. side 30" Maple	S00°E	33.43'
Remon. tag W. side 8" Pine	N30°E	43.04'
Remon. tag N. side P. Pole	S55°E	76.53'
Remon. tag E. side P. Pole	N35°W	196.6'
On C/L E-W gravel		

P.A. 345 1990 KENT COUNTY

PEER APPROVED 4/27/95

CHAIRMAN *Harry Huber*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-9 Standard Kent County Monument

Nail & KC Remon. tag E. side 30" Maple (dead)	S00°E	33.43'
Nail & KC Remon. tag N. side P. Pole	S55 E	76.53'
Nail & KC Remon. tag E. side P. Pole	N35°W	196.64'
Set Nail & KC Remon. tag E. side P. Pole	S05°W	23.74'
Set Nail & KC Remon. tag W. side P. Pole	N15°E	155.66'
On C/L E-W gravel		



Signed by *Kirk Breitels*

Date 4/20/95

Surveyor's Michigan License No. 30077