

**SURVEY & REMONUMENTATION**

**\$7.00**  
**\$2.00**

**MAR 08 1999**

**KENT COUNTY REMONUMENTATION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
98 MAY 21 AM 8:30  
REG. OF DEEDS  
*Lucy Spauld*

For corners in **SECTION**

**KENT COUNTY**  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T10N R 11W F-13  
T R  
T R  
T R
- 2. Property Controlling in Section S T R  
S T R
- 3. Miscellaneous Property in Sec. S T R  
S T R

**10597**

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breitels, in a field survey on Feb. 26, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:**

- F-13 1837 GLO Brookfield Set Post
- 1894 Williams & Works Old stake under stone 236.28' East of N 1/4 cor. Sec. 4, 9-11
- 1939 Kent Co. Wits. Concrete Monument
- 1995 LCRC #8540 Breitels Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Kirk Breitels on 8-7-95 and was recorded per LCRC #8540.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

F-13 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Kirk Breitels in place of the Concrete Monument he found. Concrete Monument checks with Williams & Works measurements and Kent Co. Wits. LCRC #8540

- Nail & Remon. tag S. side 24" Walnut N75°W 89.32'
- Nail & Remon. tag N. side 18" Ash S60°W 35.57'
- Nail & Remon. tag E. side P. Pole S20°E 49.83'
- Nail & Remon. tag SW side 10" Walnut S45°E 33.67'

P.A. 345 1998  
PEER APPROVED 4/30/98  
CHAIRMAN *Henry Kubler*

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- F-13 Standard Kent County Monument
- Nail & KC Remon. tag S. side 24" Walnut N75°W 89.29'
- Nail & KC Remon. tag N. side 18" Ash S60°W 35.55'
- Nail & KC Remon. tag E. side P. Pole S20°E 49.81'
- Nail & KC Remon. tag SW side 10" Walnut S45°E 33.67'
- Kent Co. Mon. (F-1, T9N, R11W) West 235.84'



Signed by *Kirk Breitels*  
Surveyor's Michigan License No. 30077

Date 4/30/98