

SEP 18 1995
\$7.00
\$2.00 COMMISSION

KENT COUNTY REMONUMENTATION

95 MAY 12 AM 10:45

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Eric J. Bond
REG. OF DEEDS

For corners in
KENT COUNTY
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>10N</u> R <u>11W</u>	<u>G-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

8399

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Feb. 24, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-1	1837	GLO	Cathcart	Set Post
	1928	Williams & Works		Iron & Stone
	1956	Kent Co. Wit.		1" Iron
	1985	LCRC #4384	Ochs	Set Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Norman L. Ochs on 8/13/85 and was recorded per LCRC #4384.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-1 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Norman L. Ochs on the twp. line. 3/4" Iron he found inside a mon. box checks with Williams & Works information and Kent Co. Wit.

LCRC #4384

36" W. Oak	N55°E	55.65'	Nail in face
P. Pole	S45°E	65.61'	Spk. in NE side
20" Maple	S20°W	100.19'	Spk. in NE side
Tel. Riser	S30°W	71.09'	

P.A. 345 1990 KENT COUNTY
PEER APPROVED 4/27/95
CHAIRMAN *Harry Huber*

This corner was set 1.33' North of a found 3/4" Iron Pipe in a mon. box to be on line with S 1/4 corner and SE corner of Sec. 34, Ensley Twp.

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1 Standard Kent County Monument

Spike NE side	Power Pole	S45°E	65.64'
Spike NE side	28" Maple	S20°W	100.17'
NE corner	Tel. Riser	S30°W	70.60'
Set Nail & KC	Remon. tag N. side	Power Pole	N80°E 98.88'
Set Nail & KC	Remon. tag W. side	Power Pole	N00°E 158.12'
N. edge of mon. box - South 0.94'			
On C/L road South; C/L road E-W - 1.5' South			



Signed by *Kirk Breitels*

Date 4/20/95

Surveyor's Michigan License No. 30077