

37.00  
2.00

KENT COUNTY REMONUMENTATION

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

95 MAY 12 AM 10:46

For corners in  
KENT COUNTY  
(County)

Located In: Corner Code #

1. Public Land Survey	T	10N	R	11W	G-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

*W. J. Bond*  
REG. OF DEEDS

8411

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Kirk Breiteis, in a field survey on Feb. 24, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13	1837	GLO	Cathcart	Set Post
	1959	Kent Co. Wit.		1" Iron
	1982	LCRC #3249	Hackbardt	Mon. Box
	1984	LCRC #3748	Meyer	Set Kent County Monument in mon. box

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 4/27/95  
CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Allan L. Meyer on 2/20/84 and was recorded per LCRC #3748.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13 Found standard Kent Co. Mon. (Harrison) per witnesses from above LCRC as set by Allan L. Meyer in place of the 1" Iron he found inside a mon. box. Said Iron checks with Kent Co. Wit. and LCRC #3249.

LCRC #3748

Nail & KC Remon. tag W. side 12" Sassafras	N30°E	68.82'	
Nail & KC Remon. tag N. side 8" W. Cherry	S74°E	83.77'	
Nail & KC Remon. tag NE side 30" Oak	S50°E	83.77'	(46.95' - LCRC #3249)
"X" cut top E. end 14" conc. culvert	S35°W	36.84'	
"X" cut top E. end 24" conc. culvert	North	39.47'	
SW corner 3'x 5' conc. base of MBT box	N50°E	99.35'	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13 Standard Kent County Monument

New Nail & KC Remon. tag W. side 18" Sassafras	N30°E	68.81'
New Nail & KC Remon. tag N. side 14" W. Cherry	S74°E	83.74'
New Nail & KC Remon. tag NE side 40" Oak	S50°E	47.00'
"X" cut top E. end 14" conc. culvert	S35°W	36.89'
"X" cut top E. end 24" conc. culvert	N10°E	39.49'
SW corner 3'x 5' conc. base of MBT box	N75°E	99.35'



Signed by

*Kirk Breiteis*

Date

4/20/95

Surveyor's Michigan License No. 30077