

\$7.00
\$2.00

MAY 22 2000 KENT COUNTY REMONUMENTATION

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 JUL -9 AM 11:19

REG. OF DEEDS

11232

Register of Deeds Stamp & File Number

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

1. Public Land Survey

T10N R 11W

Solon Twp.
H-7

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on May 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-7 1837	GLO	Cathcart	Set Post
1954	Kent Co. Wits		1" Iron & Stone
1973	LCRC #587	Spicer	3/4" Iron
1981	LCRC #2176	Jonker	Set Kent County Monument
1990	LCRC #5606	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 6/24/99
CHAIRMAN *Harry Huber*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10-1-81 and was recorded per LCRC #2176.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 3/4" Iron over a 3/4" Pinched Iron he found. Both Irons check with Kent Co. Wits. and LCRC #587.	
LCRC #2176	LCRC #5606
Nail & Remon. tag Tw. 20" Maple N10°W 26.70'	Nail & Remon. tag 15" Maple N65°E 85.47'
Nail & Remon. tag 9" Pine S30°W 23.86'	Nail & Remon. tag 16" Tamer. N65°W 98.47'
Nail & Remon. tag 9" Maple N72°E 86.50'	Nail & Remon. tag 30" Oak S60°W 96.76'
Nail & Remon. tag 12" Maple S73°W 58.67'	Nail & Remon. tag 10" Oak S30°W 65.03'
On fence line to North	Nail & Remon. tag 12" Oak S05°W 65.27'
C/L gravel 2' North	

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 Standard Kent County Monument	
Nail & KC Remon. tag S. side 18" Maple	N65°E 86.43'
Nail & KC Remon. tag N. side 18" Tamarack	N65°W 98.40'
Nail & KC Remon. tag E. side 15" Oak	S05°W 65.53'
Nail & KC Remon. tag N. side 14" Oak	S60°E 62.53'
Nail & KC Remon. tag N. side P. Pole	S80°W 105.33'
Nail & KC Remon. tag W. side 12" Beech	N00°E 41.47'
C/L new E-W asphalt road is North 4'	



Signed by *Kirk Breitels*
Surveyor's Michigan License No. 30077

Date 6/24/99