

\$7.00
\$2.00

MAY 28 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located in:

Corner Code #

Solon Twp.

H-11

1. Public Land Survey

T10N R 11W

T R

T R

T R

T R

2. Property Controlling in Section

S

T R

S

T R

3. Miscellaneous Property in Sec.

S

T R

S

T R

REG. OF DEEDS

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:00

11089

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 18, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

H-11 1837	GLO	Cathcart	Set Post
1940	Kent Co. Wits		Conc. Mon. & Iron
1975	LCRC #890	Nederveld	1" Iron
1981	LCRC #2131	Jonker	Set Kent County Monument in Mon. Box
1990	LCRC #5608	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN Harry Huber

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9-22-81 and was recorded per LCRC #2131.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-11 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1" Iron he found over a Conc. Mon. inside a Mon. Box. Both check with Kent Co. Wits. and LCRC #890.

LCRC #2131	Nail & Remon. tag P. Pole	South	46.66'	LCRC #5608	Nail & Remon. tag 10" Oak	N25°W	44.69'
	Nail & Remon. tag 48" Oak	N50°W	61.80'		Nail & Remon. tag P. P.	S00°W	46.63'
	Nail & Remon. tag 12" Oak	S69°W	73.19'		Nail & Remon. tag 48" Oak	N50°W	61.80'
	Nail & Remon. tag 16" Maple	S25°W	100.08'		Nail & Remon. tag Tw. Maple 16"-12"	S25°W	99.92'

C/L E-W B.T. is 1' North
On line tree & fence line to South

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-11 Standard Kent County Monument	Nail & KC Remon. tag W. side 12" Oak	N25°W	44.82'
	Nail & KC Remon. tag E. side P. Pole	S00°W	46.60'
	Nail & KC Remon. tag SW side 56" Oak	N50°W	61.82'
	Nail & KC Remon. tag E. side Tw. 18"-14" Maple	S25°W	100.03'
	Nail & KC Remon. tag NW side 12" Elm	N50°E	58.31'
	On fence tree line to South ±		
	C/L E-W pavement is 1' North ±		



Signed by Kirk Breitels

Date 2/25/99

Surveyor's Michigan License No. 30077