

MAY 22 2000

\$7.00
\$2.00

SECTION KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY
(County)

Located In:	Corner Code #
Solon Twp.	I-2
T10N R 11W	
T___ R___	
T___ R___	
T___ R___	
S___ T___ R___	
S___ T___ R___	
S___ T___ R___	
S___ T___ R___	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

1999 MAR 24 AM 8:50

REG. OF DEEDS

11090

Register of Deeds Stamp & File Number

I, Kirk Breitels, in a field survey on Jan. 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3	●	2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

I-2	1837	GLO	Cathcart	Set Post
	1961	Kent Co. Wits		Stone & Iron
	1975	LCRC #840	Chambers	1 1/2" Iron
	1981	LCRC #1746	Merdzinski	Set Kent County Monument
	1990	LCRC #5609	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN Harry Tubert

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John A. Merdzinski on 1-6-81 and was recorded per LCRC #1746.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- I-2 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John A. Merdzinski in place of the 1 1/2" Pipe he found. Said 1 1/2" Pipe checks with LCRC #840 & Kent Co. Wits.
- | | |
|--|---|
| LCRC #1746 | LCRC #5609 |
| Nail & Remon. tag 22" Tw. Oak N15°W 13.56' | Nail & Remon. tag 34" Oak N10°W 13.49' |
| Nail & Remon. tag P. Pole N75°W 28.91' | Nail & Remon. tag 34" Oak N35°E 35.45' |
| Nail & Remon. tag 18" Tw. Oak N25°E 32.54' | Nail & Remon. tag 28" Oak ~S80°E 44.45' |
| Nail & Remon. tag 24" Oak S85°E 44.56' | Nail & Remon. tag 14" Ash S35°E 40.87' |
| Nail & Remon. tag T. Pole S20°E 37.48' | |
| Nail & Remon. tag T&P Pole S40°W 48.83' | |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-2 Standard Kent County Monument
- Nail & KC Remon. tag W. side 36" Oak N10°W 13.49'
- Nail & KC Remon. tag S. side 36" Oak N35°E 32.50'
- Nail & KC Remon. tag N. side 30" Oak S80°E 44.50'
- Nail & KC Remon. tag NE side 16" Ash S35°E 40.95'
- Nail & KC Remon. tag E. side P. Pole S00°E 25.73'
- C/L private dr. E'y & W'y is South 13' ±



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/25/99