

\$7.00
\$2.00

MAY 28 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
KENT COUNTY

(County)

Located in:

Corner Code #

Solon Twp.

1. Public Land Survey

T10N R 11W

I-4

T R

T R

T R

T R

2. Property Controlling
in Section

S T R

S T R

3. Miscellaneous
Property in Sec.

S T R

S T R

REG. OF DEEDS

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:00

11092

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 14, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10	●	11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-4	1837	GLO	Cathcart	Set Post
		Kent Co. Wits		Witnesses only given
	1978	LCRC #1202	Jonker	1" Iron
	1981	LCRC #2130	Jonker	Set Kent County Monument
	1990	LCRC #5578	Marschall	Kent County Monument
	1993	LCRC #6812	W. Glaza	Reset Kent County Monument after construction

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9-25-81 and was recorded per LCRC #2130.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1" Iron & Stone he found. Both Iron & Stone check with LCRC #1202 & Kent Co. Wits.

LCRC #2130	LCRC #5578	LCRC #6812
36" Oak N12°W 67.47'	40" Oak N12°W 67.43'	18" Oak N50°W 49.60'
12" Hickory N58°W 16.15'	18" Hickory N60°W 16.06'	38" Oak N20°W 67.47'
24" Maple N30°E 73.75'	30" Maple N25°E 73.75'	26" Maple N35°E 73.68'
Conc. fe. Post S37°E 39.81'	P. P. S50°E 47.82'	20" Hickory S50°E 61.22'
C/L N-S grav. rd. is E. 8.5'	C/L grav. rd. East 9' ±	C/L Simmons Ave. is East 3.5'
		NW corner Hse. #16500 N75°E 104.75'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4 Standard Kent County Monument

Nail & KC Remon. tag NE side 20" Oak	N50°W	49.60'
Nail & KC Remon. tag E. side 38" Oak	N20°W	67.47'
Nail & KC Remon. tag NW side 26" Maple	N35°E	73.68'
Nail & KC Remon. tag NE side 20" Walnut	S50°E	62.22'
NW corner (stone) Hse. #16500	N75°E	104.75' ±
C/L Simmons Ave. (asphalt) is East 3.5' ±		



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99