

MAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

\$7.00
\$2.00

REG. OF DEEDS

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:00

For corners in
KENT COUNTY
(County)

Located In: Corner Code #
Solon Twp.
I-8
T10N R 11W
T R
T R
T R
S T R
S T R
S T R
S T R

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

11094

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-8	1837	GLO	Cathcart	Set Post
	1964	Kent Co. Wits		Iron
	1976	LCRC #953	Bonnema	1/2" Iron
	1981	LCRC #2174	Jonker	Set Kent County Monument
	1990	LCRC #5580	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 10-1-81 and was recorded per LCRC #2174.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-8 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 2" Well Point he found. Said Well Point checks with LCRC #953 & Kent Co. Wits.

LCRC #2174	LCRC #5580
Nail & Remon. tag P. Pole N68°E 69.55'	Nail & Remon. tag P. P. N65°E 69.50'
Nail & Remon. tag P. Pole S24°E 122.89'	Top CL fire hydrant N40°E 112.55'
Nail & Remon. tag P. Pole S70°W 79.88'	Nail & Remon. tag 18"-22" Twin Oak N12°W 145.07'
C/L Street Sign N37°W 43.4'	Nail & Remon. tag P. P. S68°W 79.79'
On C/L "X" gravel	Nail & Remon. tag P. P. S30°E 122.89'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-8 Standard Kent County Monument	
Nail & KC Remon. tag S. side P. Pole	N65°E 69.50'
Top C/L ornamental fire hydrant	N40°E 112.58'
Nail & KC Remon. tag E. side Twin 24" Oak	N12°W 145.10'
Nail & KC Remon. tag N. side P. Pole	S68°W 79.67'
Nail & KC Remon. tag SW side P. Pole	S30°E 122.89'
On C/L asphalt roads ±	



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99