

\$7.00  
\$2.00

MAY 22 2000

# KENT COUNTY REMONUMENTATION

SECTION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Solon Twp.  
I-10

1. Public Land Survey

T10N R 11W

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

T \_\_\_ R \_\_\_

2. Property Controlling  
in Section

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_

S \_\_\_ T \_\_\_ R \_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Jan. 12, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

REG. OF DEEDS

*[Signature]*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 MAR 24 AM 8:00

11096

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

I-10 1837	GLO	Cathcart	Set Post
1969	Kent Co. Wits		1/2" Iron
1973	LCRC #374	Bonnema	1/2" Solid Rod
1975	LCRC #890	Nederveld	1/2" Solid Rod
1981	LCRC #2120	Jonker	Set Kent County Monument
1990	LCRC #5581	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY  
PEER APPROVED 2/25/99  
CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Robert J. Jonker on 9-25-81 and was recorded per LCRC #2120.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-10 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Robert J. Jonker in place of the 1/2" Solid Rod & 3/8" Solid Rod he found. Both Solid Rods check with LCRC's #374 & #890 and Kent Co. Wits.

LCRC #2120	Nail & Remon. tag P. Pole	S57°W 54.09'	Nail & Remon. tag 28" Ash	N16°W 51.39'
	Nail & Remon. tag 20" Hickory	N12°W 51.39'	Nail & Remon. tag P. P.	S52°W 54.09'
	Nail & Remon. tag top fc. post	N64°E 65.38'	Nail & Remon. tag 38" Oak	S05°W 38.17'
	Nail & MSHD. tag 34" Oak	S05°W 38.26'	Nail & Remon. tag 26" Maple	S75°W 101.82'
	C/L E-W B.T. is South 1 1/2'		Nail & Remon. tag 10" Pine	S40°E 46.06'
	Fence to N, East 1' ±			

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-10 Standard Kent County Monument			
Large Nail E. side 30" Ash	N16°W	51.19'	
Nail & KC Remon. tag S. side P. Pole	S52°W	54.09'	
Nail & KC Remon. tag top 38" Stump	S05°W	38.64'	
Nail & KC Remon. tag N. side 28" Maple	S75°W	101.67'	
Nail & KC Remon. tag N. side 12" Pine	S40°E	46.08'	



Signed by *[Signature]*  
Surveyor's Michigan License No. 30077

Date 2/25/99