

SECTION
MAY 22 2000

\$7.00
\$2.00

SECTION KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY
(County)

Located in:

Corner Code #

Solon Twp.

- 1. Public Land Survey T 10N R 11W I-12
- T R
- T R
- T R
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R

REG. OF DEEDS

[Signature]

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
1999 MAR 24 AM 8:08

11097

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Kirk Breitels, in a field survey on Feb. 18, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- I-12 1837 GLO Cathcart Set Post
- 1887 Williams & Works Iron
- 1917 RR Map Corner 6' North of tracks
- Kent Co. Wits Iron
- 1982 Survey Exxel Eng. Set Iron
- 1992 LCRC #6592 Bueche Set Kent County Monument

P.A. 345 1990 KENT COUNTY
PEER APPROVED 2/25/99
CHAIRMAN [Signature]

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by John C. Bueche on 10-12-92 and was recorded per LCRC #6592.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-12 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by John C. Bueche in place of the Iron (Exxel) he found. Said Iron checks with Williams & Works information ± and Exxel Eng. information.
LCRC #6592

- Nail W. side group 8" Maples N20°E 7.20'
- Nail NW side 22" Pine South 46.32' 8' North of old RR bed.
- Nail NW side 24" Pine S50°W 76.00'
- Nail & Remon. tag S. side 6" Cherry N85°E 57.00'
- Nail & Remon. tag E. side Tri. 18" Cherry N35°W 37.60'
- Exxel Iron North 24.70'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-12 Standard Kent County Monument
- Nail & KC Remon. tag W. side group 8" Maples N20°E 7.13'
- Nail W. side 22" Pine South 46.42'
- Nail NW side 24" Pine S50°W 76.03'
- Nail & KC Remon. tag S. side 8" Cherry N85°E 57.02'
- Nail & KC Remon. tag E. side Tri. 24" Cherry N35°W 37.60'
- Capped Rerod (Exxel) North 24.70'
- C/L old RR bed is North 8' ±



Signed by [Signature]
Surveyor's Michigan License No. 30077

Date 2/25/99