

SURVEY & REMONUMENTATION

MAR 08 1999

KENT COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION _____

For corners in

KENT COUNTY
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|-----------------------------|-------------|
| 1. Public Land Survey | T <u>10</u> N R <u>11</u> W | <u>I-13</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on Jan. 7, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | |
|------|------|------------------|------------|---------------------------------------|
| I-13 | 1837 | GLO | Brookfield | Set Post |
| | 1887 | Williams & Works | | Set Stake, Iron, Earthenware |
| | 1893 | Williams & Works | | Iron - 168.96' East of I-1, T9N, R11W |
| | 1966 | MDSH | Spencer | Set Bolt by single pro. meas. |
| | 1971 | Williams & Works | | Iron - 169.00' East of I-1, T9N, R11W |
| | 1995 | LCRC #8542 | Breitels | Set Kent County Monument |

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Kirk Breitels on 8-7-95 and was recorded per LCRC #8542.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13 Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Kirk Breitels in place of the Iron Pipe he found. Said Iron checks with Williams & Works and MDSH information.

- | | | | |
|------------|---|-------|---------|
| LCRC #8542 | Nail & MDSH tag W. side P. Pole | N05°E | 62.86' |
| | Nail & KC Remon. tag W. side 30" Maple | N00°W | 31.50' |
| | Nail & KC Remon. tag NE side 30" Walnut | N60°W | 57.42' |
| | Nail & KC Remon. tag W. side 30" Maple | S60°E | 45.73' |
| | Nail & KC Remon. tag NW side 24" Maple | S45°W | 39.73' |
| | Kent Co. Mon. (I-1, T9N, R11W) | West | 168.95' |

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | | |
|------------------------------------|---|-------|---------|
| I-13 Standard Kent County Monument | Nail & MDSH W. side P. Pole | N05°E | 62.86' |
| | Nail & KC Remon. tag W. side 30" Maple | N00°W | 31.50' |
| | Nail & KC Remon. tag NE side 30" Walnut | N60°W | 57.42' |
| | Nail & KC Remon. tag W. side 30" Maple | S60°E | 45.73' |
| | Nail & KC Remon. tag NW side 24" Maple | S45°W | 39.73' |
| | Kent Co. Mon. (I-1, T9N, R11W) | West | 168.95' |

P.A. 345 1990 KENT COUNTY

PEER APPROVED 2/19/98
CHAIRMAN Harvey Huber

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD
99 MAR -5 AM 8:35
REG. OF DEEDS
Lucy Stank

10587

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 2/19/98