

\$7.00  
\$2.00

MAY 22 2000

KENT COUNTY REMONUMENTATION

SECTION LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Solon Twp.

1. Public Land Survey	T <u>10</u> N R <u>11</u> W	J-1
	T <u>   </u> R <u>   </u>	_____
	T <u>   </u> R <u>   </u>	_____
	T <u>   </u> R <u>   </u>	_____
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	_____
	S <u>   </u> T <u>   </u> R <u>   </u>	_____
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	_____
	S <u>   </u> T <u>   </u> R <u>   </u>	_____

REG. OF DEEDS

*[Signature]*

STATE OF MICHIGAN  
COUNTY OF KENT  
RECEIVED FOR RECORD  
1999 NOV - 4 AM 8:35

11468

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Kirk Breitels, in a field survey on Oct. 11, 19 99 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-1	1837	GLO	Cathcart	Not Set
	1923	Williams & Works		Set Iron
	1932	Kent Co. Wits		Iron
	1985	LCRC #4294	Meyer	3/4" Iron in Mon. Box
	1985	LCRC #4387	Ochs	Set Kent County Monument
	1990	LCRC #5582	Marschall	Kent County Monument

P.A. 345 1990 KENT COUNTY

PEER APPROVED 10/28/99  
CHAIRMAN *[Signature]*

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Norman L. Ochs on 10-23-85 and was recorded per LCRC #4387.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-1 AFTER ROAD CONSTRUCTION, Set Kent County Monument (Harrison) in Mon Box on Twp. Line per witnesses from above LCRC as set on Twp. Line by Norman L. Ochs in place of the 1/2" & 3/4" Pipes in a Mon. Box he found. Both check with Williams & Works, Kent Co. Wits. and LCRC #4294.

LCRC #4387	LCRC #5582
Spike in 22" Maple N15°E 57.32'	Nail & Remon. tag 38" Walnut N75°W 105.27'
Spike in 6" Walnut N10°W 79.28'	Nail & Remon. tag 12" Walnut N18°W 79.24'
PK Nail in 28" Walnut N80°W 105.33'	Nail & Remon. tag 28" Maple N22°E 57.19'
C/L top Tel. Riser S40°E 52.69'	SE cor. porch (conc. Floor) N10°E 100.52'
	Tel. Riser S45°E 52.77'

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-1 Standard Kent County Monument in Mon. Box	
Nail & KC Remon. tag S. side 40" Walnut	N75°W 105.31'
Nail & KC Remon. tag W. side 15" Walnut	N18°W 79.29'
Nail & KC Remon. tag E. side 30" Maple	N22°E 57.58'
SE corner porch - concrete floor	N10°E 100.58'
Nail & KC Remon. tag NE side 4" Oak	S40°E 76.64'
SE corner Sec: 35-11-11 (Newaygo Co. Mon.)	West 179.41'



Signed by *[Signature]*  
Surveyor's Michigan License No. 30077

Date 10/28/99