

3/2

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF KENT
REC'D
93 AUG 21 1993

For corners in

Kent
(County)

Located In:

Corner Code //

- 1. Public Land Survey T 10N R 11W J-2
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

Seg #1

6814

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3					
3												
4	7		8		9		10		11		12	
5												
6	16		17		18		19		20		21	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Wallace E. Glaza, in a field survey on August 12, 19 93 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-2 Williams & Works (1952) set iron at center of Section 3390.9' South of North $\frac{1}{4}$ corner.

- 18" Elm West 3.0'
- 12" Double Oak SSW 25.85'
- 20" Elm NE 22.57'
- 10" Elm East 12.78'

LCRC No. 4548 (Glen Hackbardt) 1 $\frac{1}{2}$ " iron

- 10" Maple South 28.45' 10" Maple S75°E 12.65'
- 8" Maple S30°E 20.3' 12" Maple S80°W 24.45'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-2 (Center of Section 2, T10N, R11W, Solon Township, Kent County, Michigan.)

Found iron as per above witness. Iron is 6.58' East and 0.85' South of intersection of $\frac{1}{4}$ lines. Corner has been used by several surveyors. Accepted iron as center of Section.

Replaced iron with standard 4" x 30" Harrison Monument.

- South $\frac{1}{4}$ to center - 2658.11'
- West $\frac{1}{4}$ to center - 2685.07'
- North $\frac{1}{4}$ to center - 3388.90'
- East $\frac{1}{4}$ to center - 2684.46'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-2 (Standard 4" x 30" Harrison Monument)

- 1) Nail and tag in N side 24" Oak N90°E 50.81'
- 2) Nail and tag in NE side 12" Maple S30°E 20.37'
- 3) Nail and tag in E side 14" Oak S00°E 35.80'
- 4) Nail and tag in S side 12" Maple S90°W 24.49'
- 5) Waters edge of Middle Lake N00°E 40'±



Signed by Wallace E. Glaza
Glaza and Associates, Inc. 31592

Date 8-17-93