

\$7.00
\$2.00

MAY 28 2000

KENT COUNTY REMONUMENTATION

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

KENT COUNTY

(County)

Located In:

Corner Code #

Solon Twp.

1. Public Land Survey

T 10N R 11W

J-5

T R

T R

T R

T R

2. Property Controlling in Section

S T R

S T R

3. Miscellaneous Property in Sec.

S T R

S T R

REG. OF DEEDS

1999 JUL -9 AM 11:19

STATE OF MICHIGAN
COUNTY OF KENT
RECEIVED FOR RECORD

11239

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Kirk Breitels, in a field survey on May 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

J-5	1837	GLO	Cathcart	Set Post
		1912-47 Williams & Works		Held computed corner per 1/8 corner dimensions.
		1984 LCRC #3794	Kolehouse	Set Kent County Monument per 1912-47 measurements.
		1990 LCRC #5614	Marschall	Kent County Monument

The position of this corner was previously approved by the Kent County Remonumentation Peer Group, monumented by Randy J. Kolehouse on 3-30-84 and was recorded per LCRC #3794.

P.A. 345 1990 KENT COUNTY

PEER APPROVED

CHAIRMAN Henry Huber

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

J-5	Found Kent County Monument (Harrison) per witnesses from above LCRC as set by Randy J. Kolehouse.		
LCRC #3794	LCRC #5614		
Nail & Remon. tag 14" Oak	S45°W 45.45'	Nail & Remon. tag 16" Oak	S45°W 45.42'
Nail & Remon. tag 8" Oak	S85°W 13.02'	Nail & Remon. tag 10" Maple	S85°W 13.02'
Nail & Remon. tag 16" Maple	West 21.80'	Nail & Remon. tag 18" Oak	S90°W 21.73'
Nail & Remon. tag 16" Oak	S10°W 38.45'	Nail & Remon. tag 20" Oak	S10°W 38.46'
Nail & Remon. tag Tw. 8" Maple	S15°W 13.02'	Nail & Remon. tag Tw. 12"-10" Maple	S15°W 12.97'
"T" Iron East	674.7'		

The selected location is accepted by me and is generally accepted by professional surveyors as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-5	Standard Kent County Monument*		
Nail & KC Remon. tag SE side	18" Oak	S45°W	45.42'
Nail & KC Remon. tag S. side	12" Maple	S85°W	13.02'
Nail & KC Remon. tag N. side	20" Oak	S90°W	21.71'
Nail & KC Remon. tag W. side	22" Oak	S10°W	38.44'
Nail & KC Remon. tag E. side	Tw. 12"-10" Maple	S15°W	12.97'
SW corner wood "deer blind" leg		N45°E	7.1'



Signed by Kirk Breitels
Surveyor's Michigan License No. 30077

Date 6/24/99